

STEP 1: INSTALL THE HARDWARE

Step 1

Remove retainer screw from panel top





Pull back plate off gently




Step 3

Mount back plate to wall



Step 4

Hook panel stabilizer strap onto back plate



Step 5

Connect battery DO NOT DISCONNECT AFTER INSTALLATION

Step 6



Connect wires. DCIN+ to Positive DCIN- to Negative

Step 7

Positive to +

Negative to -



Connect power supply



Step 8

Plug in power supply and secure with screw. Flip bracket upside for decor style plugs.



Tilt panel upward onto back plate until it snaps in place



Replace retainer screw and tighten

STEP 2: CONNECT WI-FI







Wireless Settings

Touch "Wireless Settings"

Wi-Fi Settings Select network

Touch "Wi-Fi Settings"

Select the desired network.

> Enter Wi-Fi password if required.

*Requires Installer code, default is "1111"

STEP 3: RUN A CELL TEST



Settings



Test



Cellular Test Start Cancel

Touch "Start" to begin the test

Cellular radio test started. Please walt...
rellular wireless bath tested successfully. Call Central Station to check reports if needed.

Successful results will initiate a panel download from the Alarm.com servers, like date, local time, weather, etc., and begins syncing your company's contact info & template settings. Alarm.com account must be created prior to test.

STEP 4: CHECK FOR SOFTWARE UPDATES



Settings



Installation



Upgrade Software

Upgrade Using Network Search network for updates and install new software

Touch "Upgrade using Network"

If update is available it will download and install automatically. Once complete, touch "OK" to restart the panel.*

OK

*NOTE: Download could take could take up to 3 minutes, depending on your connection speed. After the panel re-starts DO NOT TOUCH THE PANEL for 5 minutes to allow the software to fully install.

STEP 5: PAIR SECURITY & LIFE SAFETY SENSORS



Settings





AutoLearn Security Sensor Sensors



'Tamper'' Sensor Typically done by opening case, see manual for specifics



chime and a message will appear. Touch "OK"



Select a quick name or custom.

Add

Touch

"Add"

NOTE: Image Sensors are placed in "pairing mode" by removing and replacing the batteries. See installation manual for details.

STEP 6: PAIR Z-WAVE DEVICES







Installation




Home Control **Devices**



Add Device



Touch "Pair"





Press "Learn button on device



Device information appears automatically. Edit as desired.



Touch "Add" to complete the pairing process.

NOTE: If the device does not learn in you may need to "Clear Device" first. See installation manual for detailed steps

IMPORTANT

FOR DETAILED INSTRUCTIONS REFER TO THE IQ PANEL INSTALLATION MANUAL ON DEALERS.QOLSYS.COM

Security Signaling Residential Fire Alarm and **Security Equipment**

ETL Listed

Conforms to ANSI/UL Standards Conforms to ANSI/UL Std. S985. 1023. & 1635 Certified to ULC Sub. C1023 & ULC Std. S545

Document#: IQPANEL-QG-01-15 Revision Date: 5/1/15 Applies to Qolsys Part #s:

QS-9004-VRZ QS9014-124-00-04 QS9004-840-00-00 QS9014-484-00-06 QS9014-840-00-02







Qolsys Inc. proprietary. Reproduction without permission is not permitted.

ALL IN ONE. ALWAYS CONNECTED























There may be new features available for this IQ Panel.

After installation is complete follow the instructions inside for connecting to Wi-Fi and performing a software update.



